



# OFFICE OF THE PRINCIPAL N.C.COLLEGE, BADARPUR

NC/RUSA/Renovation/Quotation/2017/01

Date: 13-05-2017

## NOTICE

Sealed quotations are invited in prescribed format(available in college) from Govt. Regd. Contractor of appropriate class for the work of renovation of first floor of old Academic & Administrative building of N.C. College, Badarpur of approx are of 8000 sq ft which includes following items of works in broad classification with a time limit of 45 days.


- (i) Removal of flooring and supply, fitting and fixing of 800 mm X 800 mm vitrified floor tiles of NITCO make of premium quality in the entire floor as fitted in ground floor.
- (ii) Construction of new RCC Toilet block for girls in girls Common Room, Library Room of size shown in drawing as per requirement and standard specification along with water supply and sanitary fittings.
- (iii) Supply, fitting and fixing of antiskid vitrified floor tiles in floor of toilet block and vitrified wall tiles in walls of toilet block as per requirement and specification of the college authority.
- (iv) Dismantling of walls of Teacher's Common Room and renovation of the room along with false ceiling (Gypsum board) in the Common Room as per drawing given by the college.
- (v) Removal of old paints of the wall and ceiling of the first floor and application of wall putty along with supply in internal and external walls. After application of putty plastic painting of approved brand will be applied in internal walls & weather coat painting of approved brand will be applied in external wall along with supply of paints.
- (vi) All the doors and windows are to be repaired wherever required and painted with enamel paint of approved brand. All the grills are to be painted with approved brand of enamel paint along with supply of paints.
- (vii) Renovation of walls of Library and Girls Common Room are to be done as per requirement of College including new brick wall, lintel etc along with plastering.
- (viii) In Library room Aluminum partition counter are to be constructed as per drawing and as done in ground floor. One glass partition wall has to be constructed for digital library as shown in the drawing.

- (ix) All the electrical wiring has to be changed and fitted again as per requirement of college with new plug points, switches, cables & accessories.
- (x) Dismantling of old walls of toilet block of Teachers Common Room including lintel etc and renovation of the same for Ladies and Gents toilet as per requirements of the college authority including supply, fitting and fixing of wall and floor tiles of required specification.
- (xi) Marble flooring is to be provided in staircase with supply of Dungri class marble of appropriate size & specification from ground floor to first floor.

All the contractors are required to deposit a non refundable fee Rs 4000.00 to the college along with application. The Contractor must possess modern electrical machine for wall cutting and all other machines for concreting and wooden work. The contractor must verify the scope of works from college authority before submission of quotation. The Contractor must submit valid Regn. Certificate, PAN card, Sale tax Regn. Certificate, Experience Certificate of building construction work in Govt. Deptt. or Govt Institutions of value not less than 16 lacks along with applications. The notification also available in the college website [www.nccollege.ac.in](http://www.nccollege.ac.in) in addition to College Notice Board The last date of submission quotation is 22-05-2017 upto 2.00 p.m.

Copy to :-

1. Chairman Badarpur Town Committee for displaying in Notice Board.
2. BDO, Badarpur Development Block for displaying in Notice Board.



13/5/17

(Dr. Mortuja Hussain)  
Principal  
N.C. College, Badarpur

Principal  
NABINCHANDRA COLLEGE  
P.O. Badarpur, Dt. Karimganj (Assam)